## Spillage Testing

CTSGroup- Method Statement 2023-2026

Please use this method statement when carrying out this test

## Spillage Testing

## CTSGroup- Method Statement 2023-2026

- Close Doors and Windows to the room under test,
- 2. Turn on any extractor fans in the same or adjacent rooms. Then test with the connecting door closed, and open to confirm a satisfactory result.
- 3. Select The correct Tools and Equipment for the Job (P.s. Require Smokes Matches, Match Holder, and Manufacturer's Instructions (This Test MUST NOT be performed if the manufacturer manual is not available as it details the test requirements). Manuals are usually available online.
- 4. Turn on the gas fire or appliance under test at full rate. Press CONTINUE on the assessment Let it run and heat up for the time the M.I. Manufacturers manual requests (usually 5 mins 10 mins) no more than 15 mins altogether.
- 5. Place the smoke as requested by the Manufacturers instructions
- 6. If it fails then heat the appliance for a further 10 mins (Don't exceed 15 mins altogether over both tests). Retest If it Fails shut off and let customer know to contact a gas reg company as the appliance is Immediately Dangerous and must not be used until rectified or disconnected from the gas and capped for safety

CTS GROUP – Copyright@2023 • If you need help when doing the assessment or help on site during your job activities you can contact us for free support on 01416289980 or use the message system on our website for a fast response. Be sure to leave your contact number and name.